

# Alande Drywall

Alfonso Garduño  
 272 E Niagara Ave, Elmhurst IL 60126  
 708-369-5395  
[alandedrywall@yahoo.com](mailto:alandedrywall@yahoo.com)



CUSTOMER:

DATE: 7/8/2020  
 JOB: Burr Ridge Birth Center  
 LOCATION: 7000 South County Line Road, Burr Ridge, IL 60527

## PROPOSAL

This proposal was calculated using open shop wages and normal working hours

Description	Quantity	Unit	Total(\$)
<b>Framing</b>			<b>\$ 25,698.57</b>
Wall type P4.- (19') 2 x 4 Wood studs @16" O.C.	288.59	ft	
Wall type P6.- (19') 2 x 6 Wood studs @16" O.C.	112.76	ft	
Wall type P8.- (19') 2 x 4 Wood studs @16" O.C.	124.38	ft	
Wall type P9.- (19') 2 x 6 Wood studs @16" O.C.	15.64	ft	
A.602 (3'6") 3 5/8" Metal studs 20ga @16 o.c.	23.21	ft	
Furring.- 2 x 4 Wood studs @16" O.C.	21.42	ft	
Wood blocking	1.00	all	
Scissor lift	1.00	all	
<b>Drywall</b>			<b>\$ 22,587.21</b>
5/8" Gypsum board hanging and taping	12,602.40	ft2	
5/8" Gypsum board ceilings	420.98	ft2	
5/8" Durock	368.40	ft2	
Patching and repair existing gypsum board	3,153.90	ft2	
Scissor lift	1.00	all	
<b>Insulation</b>			<b>\$ 4,912.93</b>
Batt insulation	541.37	ft2	
<b>Acoustical ceilings</b>			<b>\$ 28,860.87</b>
Wall angle	1,293.83	ft	
ACT1.- 24"x24" Armstrong cirrus w/ 15/16" white ceiling grid	1,991.81	ft2	
ACT2.- 24"x24" Armstrong washable clean room tile w/ 15/16" white ceiling grid	1,472.92	ft2	
Scissor lift	1.00	all	
<b>Carpentry</b>			<b>\$ 8,512.35</b>
Installing door, frame and hardware	28.00	ea	
Installing bath accessories	33.00	ea	
<b>Total</b>			<b>\$ 90,571.94</b>

Exclusion: Fire caulking

To accept this proposal, please sign and return: \_\_\_\_\_

Thank you for your business!!