

# Alande Drywall

Alfonso Garduño  
 272 E Niagara Ave, Elmhurst IL 60126  
 708-369-5395  
[alandedrywall@yahoo.com](mailto:alandedrywall@yahoo.com)



CUSTOMER:

DATE: 9/18/19  
 JOB: **Bach 2 Rock**  
 LOCATION: Arlington Heights, IL

This proposal includes open shop wages and normal working hours

## PROPOSAL

Description	Quantity	Unit	Total(\$)
<b>Framing</b>			<b>\$ 25,217.54</b>
Wall type 1/6.- (16') 3-5/8" 20ga metal studs @12"OC	240.02	ft	
Wall type 3/4.- (12') 3-5/8" 20ga metal studs @24"OC, (5') 3-5/8" kickers @48"OC	128.44	ft	
Wall type 5.- (16') 3-5/8" 20ga metal studs @12"OC + 1/2" resilient channel	86.57	ft	
Wall type 7.- (12') 6" 20ga metal studs @16"OC, (5') 3-5/8" kickers @48"OC	7.51	ft	
Wall type 8.- (16') 2-1/2" 20ga hat channel @12"OC	23.55	ft	
Reception desk wall.- (3') 3-5/8" 20ga metal studs @16"OC, (4') 3-5/8" metal studs @16"OC	9.43	ft	
Door header.- (1) 3-5/8" 20ga boxed beam	61.80	ft	
Scissor lift	1.00	all	
Wood blocking	1.00	all	
<b>Insulation</b>			<b>\$ 4,917.12</b>
Sound batt insulation	6,304.00	ft2	
<b>Drywall</b>			<b>\$ 21,280.99</b>
5/8" gypsum board hanging and taping	5,492.96	ft2	
5/8" gypsum board hanging only	3,871.90	ft2	
5/8" quietrock500	3,836.32	ft2	
Scissor lift	1.00	all	
<b>Acoustical ceilings</b>			<b>\$ 10,625.15</b>
Wall angle	808.39	ft	
ACT1.- Armstrong 2x2 acoustical ceiling tile, #1713 white school zone fine fissured	1,747.42	ft2	
ACT2.- Armstrong 2x2 acoustical ceiling tile, #1713 tech black school zone fine fissured	405.65	ft2	
Scissor lift	1.00	all	

Description	Quantity	Unit	Total(\$)
<b>Miscellaneous / Carpentry</b>			<b>\$ 5,505.60</b>
Installing WD doors, lframe and hardware, labor only	16.00	ea	
Installing bath accessories, labor only	21.00	ea	
<b>Total</b>			<b>\$ 67,546.40</b>

To accept this proposal, please sign and return: \_\_\_\_\_

Thank you for your business!!